

# STCP 04-5 Issue 005 Operational Telephony

## STC Procedure Document Authorisation

Party	Name of Party Representative	Signature	Date
<del>National Grid Electricity System Operator Ltd</del> <u>The Company</u>			
National Grid Electricity Transmission plc			
SP Transmission Ltd			
Scottish Hydro-Electric Transmission Ltd			
Offshore Transmission Owners			

## STC Procedure Change Control History

Issue 001	14/03/2005	BETTA Go-Live Version
Issue 002	04/07/2005	Issue 002 incorporating PA027
Issue 003	25/10/2005	Issue 003 incorporating PA034 & PA037
Issue 004	24/06/2009	Issue 004 incorporating changes for Offshore Transmission
Issue 005	01/04/19	Issue 005 incorporating National Grid Legal Separation Changes
<u>Issue 006</u>	<u>X/X/2023</u>	<u>Issue 006 incorporating use of 'The Company' definition as made in the STC</u>

## **1.1 Scope**

1.1.1 The provision of a resilient operational telephony infrastructure is essential for the secure operation of the National Electricity Transmission System. This document details the responsibilities and obligations on NGESOThe Company, as defined in the STC and meaning the licence holder with system operator responsibilities, and each TO with regard to the management and support of this infrastructure.

1.1.2 For the purposes of this STCP, TO means:

- NGET;
- SPT;
- SHETL; and
- All Offshore Transmission Licence holders as appointed by OFGEM

In the event that specific conditions or exceptions are made in the document relating to an Onshore TO or Offshore TO these will be prefixed appropriately

## **1.2 Objectives**

1.2.1 This process specifies responsibilities and obligations on NGESOThe Company and the TOs in relation to the operational telephony infrastructure, including:

- telephony infrastructure between NGESOThe Company and TOs;
- the use of the TO's telephony infrastructure by NGESOThe Company for NGESOThe Company to communicate with Users in the TO's licensed area and to communicate with other TOs; and
- arrangements for access to NGESOThe Company telephony infrastructure at TO Control Centres and remote locations.

## **1.3 Background**

1.3.1 The telephony infrastructure is designed to provide resiliency to maximise the availability of voice communication services in line with Good Industry Practice.

1.3.2 The specific services and facilities provided to support the operation of the operational telephony infrastructure under the ownership of each TO are specified within the TO's Services Capability Specification. Service levels associated with the maintenance and restoration of

those services and facilities will be specified in the standing TO Service Restoration Proposals where appropriate.

1.3.3 ~~The NGESO~~The Company telephony infrastructure may where agreed be provided for ~~the NGESO~~The Company by a TO providing use of it's telephony infrastructure.

## **2 Key Definitions**

### **2.1 For the purposes of STCP 04-5:**

2.1.1 none

## **3 Procedure**

### **3.1 New Telephony Systems**

3.1.1 The telephony facilities to be provided at new User sites is described in STCP18-1: Connection and Modification Application.

3.1.2 At new or existing TO Control Centres, where new telephony systems are required the relevant TO will ensure that the design of the new telephony meets the requirements of STCP 18-1: Connection and Modification Application.

### **3.2 Management of Telephony Equipment**

3.2.1 ~~NGESO~~The Company shall provide a resilient telephony infrastructure between ~~the NGESO~~The Company telephony system and an agreed connection point on the TO telephony system. ~~The NGESO~~The Company telephony infrastructure shall have the following features:

- the ability to withstand the loss of any single element of the configuration in line with Good Industry Practice;
- mains supply independence in line with Good Industry Practice;
- two way emergency calling facilities; and
- priority calling over existing call connections.

3.2.2 The TO shall provide access to TO owned telephony infrastructure at the agreed connection point on the TO telephony system with:

- the ability to withstand the loss of any single element of the configuration in line with Good Industry Practice (excepting the final handset);
- mains supply independence in line with Good Industry Practice;
- two way emergency calling facilities; and
- ~~NGESO~~The Company priority calling over existing call connections.

3.2.3 When a TO is in receipt of an alarm indicating a fault, or is otherwise made aware of a fault that may affect ~~NGESO~~The Company telephony equipment at a TO location, then that TO shall notify ~~NGESO~~The Company of the alarm or fault, in accordance with STCP 02-1 Alarm, Event and Fault management.

3.2.4 When a TO is in receipt of an alarm indicating a fault or is otherwise made aware of a fault that may affect telephony equipment under TO ownership and the fault has significant

implications for NGESOThe Company or a significant reduction in resilience, then the relevant TO shall notify NGEESO of the alarm or fault.

3.2.5 The TO shall arrange for resolution of faults or alarms on TO owned telephony infrastructure in line with the standing Service Restoration Proposal where appropriate.

3.2.6 Where NGESOThe Company is in receipt of an alarm indicating a fault or is otherwise made aware of a fault, that may affect telephony equipment under TO ownership then NGESOThe Company shall notify the relevant TO of the alarm or fault.

3.2.7 Where TO telephony equipment installed on a User site has failed, NGESOThe Company shall ensure that the User shall advise the relevant TO, and that User shall provide the TO service provider with appropriate access.

### **3.3 Change Management**

3.3.1 NGESOThe Company or the relevant TO will each provide the other Party with notification of proposed changes that the proposing Party deems may have a significant impact on its ability to provide a telephony infrastructure as outlined in 3.2.1 or 3.2.2 as appropriate.

### **3.4 Outage Coordination**

3.4.1 NGESOThe Company or the relevant TO will each provide the other Party with notification of a significant outage on it's telephony infrastructure that the notifying Party deems to have a significant impact on it's ability to provide a telephony infrastructure as outlined in 3.2.1 or 3.2.2 as appropriate.

### **3.5 Site Access and Support Arrangements**

3.5.1 Site access and support arrangements between NGESOThe Company and the relevant TO will allow ~~the~~ NGESOThe Company service provider reasonable access to NGESOThe Company's telephony infrastructure at TO sites.

3.5.2 Support arrangements with associated levels of service as part of the standing TO Service Restoration Proposals will be in place between NGESOThe Company and the relevant TO to enable restoration or maintenance of the TO telephony infrastructure as required.


3.5.3 Where Generator or User consent for access to non-TO sites is required NGESOThe Company shall procure all necessary consents.

### **3.6 Telephony Infrastructure Reporting**

3.6.1 Widespread failure of the telephony infrastructure may be assessed and reported in line with STCP 03-1 Post Event Analysis and Reporting.

**Appendix A: Flow Diagram**

Note that the Process Diagrams shown in this Appendix A are for information only. In the event of any contradiction between the process represented in this Appendix and the process described elsewhere in this STCP, then the text elsewhere in this STCP shall prevail.



## ***Appendix B: Abbreviations & Definitions***

### ***Abbreviations***

SPT	SP Transmission Limited
SHETL	Scottish Hydro-Electric Transmission Limited
TO	Transmission Owner

### ***Definitions***

#### ***STC definitions used:***

National Electricity Transmission System

Generator

Good Industry Practice

NGET

~~NGESO~~The Company

Party

Services Capability Specification

Services Restoration Proposals

Transmission

User

#### ***Grid Code definitions used:***

Control Centre